

# ROOFING CONSULTANT'S REPORT

Sentinel Roof Consulting · Our reference SRC-2025-0619

---

## INSTRUCTIONS

|                  |                                                                           |
|------------------|---------------------------------------------------------------------------|
| Instructed by:   | Coastline Brantley Insurance Advisors                                     |
| On behalf of:    | Tidewater Roofing & Exteriors, LLC                                        |
| Policy number:   | GL-3376-90284                                                             |
| Author:          | Aurelio Bekele-Thornton, RRC                                              |
| Instructed by:   | Suffolk City Public Schools as owner's representative                     |
| Instructed on:   | 19 June 2025                                                              |
| Site attendance: | 19 June 2025                                                              |
| Scope:           | Whether the open area was protected to the standard the contract requires |

## THIRD-PARTY PROPERTY AFFECTED

|                            |                                                    |
|----------------------------|----------------------------------------------------|
| Classrooms C-104 to C-111: | Ceiling grid, VCT flooring, drywall, casework      |
| Media centre:              | 2,400 sq ft, carpet, 1,850 volumes, 28 Chromebooks |
| Corridor C:                | Ceiling tile and four troffers over 120 lin ft     |
| C-wing electrical closet:  | Two 277/480V lighting panels de-energised          |
| Fire alarm:                | Eight detectors in trouble, 36-hour fire watch     |

# ROOFING CONSULTANT'S REPORT

Circumstances and findings

---

## CIRCUMSTANCES

Circumstances:

A phased TPO re-roof of a single-storey academic wing under a summer-recess contract. The system is mechanically fastened; no torch, kettle or open flame is used. All labour on 18 June was the contractor's own.

## FINDINGS

Findings:

The contractor's daily record shows a National Weather Service forecast check at 06:15 returning a 30% probability of precipitation for the work period. The tear-off quantity of 9,400 sq ft is consistent with the crew's demonstrated dry-in capability of about 10,000 sq ft per day. Dry-in photographs were taken at 09:20, 13:05 and 16:35. The 6,200 sq ft that had been mechanically fastened and lapped did not leak; every point of entry is within the 3,200 sq ft that had not been reached when the cell arrived. In this consultant's opinion the contractor's sequencing was reasonable and the storm was not forecast at a probability that should have stopped the tear-off.

|                     |                                                                  |
|---------------------|------------------------------------------------------------------|
| Date of loss:       | <b>18 June 2025</b>                                              |
| Cause of loss:      | <b>Water damage — rain into a roof left open during tear-off</b> |
| Incident reference: | <b>SCPS-2025-RF-011</b>                                          |
| Injuries reported:  | <b>0</b>                                                         |

# ROOFING CONSULTANT'S REPORT

Preliminary quantum and reserve advice

---

## PRELIMINARY QUANTUM

Basis:

The figures below are preliminary and are given for reserving purposes only. They are subject to verification and may move as the investigation continues.

|                                                 |                    |
|-------------------------------------------------|--------------------|
| Building interior, eight classrooms:            | <b>USD 268,000</b> |
| Electrical, lighting, fire alarm and fire water | <b>USD 74,000</b>  |
| Library volumes and media centre contents       | <b>USD 61,000</b>  |
| Computer carts and devices:                     | <b>USD 19,000</b>  |
| Cleaning, drying and mitigation:                | <b>USD 88,000</b>  |
| Estimated loss:                                 | <b>510,000</b>     |
| Currency:                                       | <b>USD</b>         |

## ON THE OPEN ROOF CONDITION

Comment:

The liability policy conditions water damage cover on daily forecast checking, not opening more roof than can be dried in, mechanically fastened temporary covering and daily photographs. On the documents produced, each limb is satisfied. The sublimit rather than the exclusion should therefore apply.

## RECOMMENDATION

Recommendation:

Complete drying before reinstatement begins. Re-inspect the deck fastener pattern in the saturated area before the new system is laid.