

RESTORATION CONTRACTOR'S ASSESSMENT

Sagebrush Restoration · Our reference SR-2026-1188

INSTRUCTIONS

Instructed by:	Harkness-Vaillancourt Insurance Agency
On behalf of:	Kestrel Ridge Holdings, LP
Policy number:	
Author:	Corinne Adeyemi-Vasquez, IICRC WRT/ASD
Instructed by:	Aspenwall Commercial Realty, LLC
Instructed on:	2 March 2026, 07:40
Site attendance:	2 to 6 March 2026, ongoing
Scope:	Emergency mitigation, drying and scope of reinstatement

AFFECTED SUITES

Suite 116 — vacant:	Point of entry, copper stripped from plenum
Suite 114 — Willow & Cedar Bath Co.:	Ceiling collapse over 600 sq ft, stock saturated
Suite 112 — vacant:	Drywall saturated to 4 ft
Suite 110 — Arbor & Ash Salon:	Rear shampoo area, drywall and cabinetry
Building 01 fire alarm panel:	Water at the terminal strip, trouble condition

RESTORATION CONTRACTOR'S ASSESSMENT

Circumstances and findings

CIRCUMSTANCES

Circumstances:

A neighbourhood retail centre of four buildings. The affected run is Building 01, in-line retail, Suites 100 to 118. Two suites in that run were vacant at the date of loss under a written vacancy permit requiring weekly secured and heated inspections; the last logged inspection was 27 February.

FINDINGS

Findings:

Water tracked from the severed 2-inch line above the Suite 116 plenum along the demising walls into Suites 114, 112 and 110 and into the rear corridor. Moisture mapping on arrival recorded 38% to 44% WME in the Suite 114 ceiling grid and wall base, 31% to 39% in Suite 112, and 22% to 28% at the Suite 110 shampoo wall. Twenty-two air movers, six dehumidifiers and containment were placed. Photographs were taken before any equipment was set, as the policy requires. Cabinetry in Suite 110 and the Suite 114 ceiling grid are not salvageable.

Date of loss:	2 March 2026
Cause of loss:	Theft of copper, and water damage consequent on a cut live water line
Incident reference:	ACR-2026-0302
Injuries reported:	0

RESTORATION CONTRACTOR'S ASSESSMENT

Preliminary quantum and reserve advice

PRELIMINARY QUANTUM

Basis:

The figures below are preliminary and are given for reserving purposes only. They are subject to verification and may move as the investigation continues.

Emergency mitigation, extraction and drying	USD 55,000
Building reinstatement, four suites and common areas	USD 185,000
Plumbing and electrical re-pipe and re-wire	USD 74,000
RTU refrigerant line sets, whips, condensers	USD 38,000
Fire alarm panel and devices:	USD 22,000
Estimated loss:	425,000
Currency:	USD

ON THE SPLIT BETWEEN LANDLORD AND TENANT

Comment:

Tenant improvements in Suite 114 were installed at the tenant's expense under the lease and are excluded from the figures above, as is tenant stock. The landlord scope is the shell, the ceiling grid, the base building MEP and the common corridor.

RECOMMENDATION

Recommendation:

Continue drying to a stable standard before any reinstatement. Replace rather than clean the Suite 114 ceiling grid.