

LIFTING INCIDENT REPORT

Chesapeake Rigging & Crane · Our reference CRC-2025-0826

INSTRUCTIONS

Instructed by:	Coastline Brantley Insurance Advisors
On behalf of:	Tidewater Roofing & Exteriors, LLC
Policy number:	
Author:	Anselm Kirchhoff-Adeyemi, Lift Director
Prepared for:	Tidewater Roofing & Exteriors, LLC and its insurers
Prepared on:	27 August 2025
Crane:	90 ton hydraulic, operator and signal person supplied by this company
Scope:	Sequence of the lift and the point of contact

THIRD-PARTY PROPERTY AFFECTED

Owner of the property:	Chandler Vale Cold Chain Solutions, tenant of Suite 400
Building owner:	Hampton Roads Logistics Center Owner, LLC — certificate holder
Condensing units:	Four, process refrigeration, not the building's units
Refrigerant:	Approximately 140 lb R-448A vented
Consequence:	22,000 sq ft temperature-controlled area lost cooling

LIFTING INCIDENT REPORT

Circumstances and findings

CIRCUMSTANCES

Circumstances:

The building is a 640,000 sq ft logistics facility, fully occupied and operating with three tenants running 24/7 distribution. The insured is approximately 60% through a phased TPO re-roof for the building owner. Roof Section 7 had not been torn off; the lift was staging material for it.

FINDINGS

Findings:

The pick was within the load chart at 38% of rated capacity and a written lift plan was in force. The load path passed within approximately 4 metres of the Suite 400 tenant's rooftop condensing bank. On the traverse the load contacted the guy wires on the eastern unit and then the unit housings, and dragged across the bank before the operator arrested the swing. Nothing was dropped. The contributing factor is the load path, not the machine or the rigging: the tenant's equipment was inside the swing radius and the lift plan did not exclude it. The crane has been taken out of service for inspection and the operator has provided a written statement.

Date of loss:	26 August 2025
Cause of loss:	Impact — crane load swung into a tenant's rooftop condensing units
Incident reference:	TWR-HRLC-2025-0826
Injuries reported:	0

LIFTING INCIDENT REPORT

Preliminary quantum and reserve advice

PRELIMINARY QUANTUM

Basis:

The figures below are preliminary and are given for reserving purposes only. They are subject to verification and may move as the investigation continues.

Four condensing units, two likely beyond repair	USD 35,000
Refrigerant recovery, recharge and leak testing	USD 18,000
Rooftop piping, insulation, disconnects and valves	USD 22,000
Aluminium rooftop walkway:	USD 7,000
Temporary cooling — spot coolers and fans	USD 40,000
Estimated loss:	182,000
Currency:	USD

ON THE RE-SEQUENCING

Comment:

All crane operations on the project were stopped pending review and hoisting has been re-sequenced to the north side, away from tenant equipment. That should have been the sequence from the outset given the occupancy.

RECOMMENDATION

Recommendation:

Do not resume hoisting over any occupied tenant's rooftop plant. Re-issue the lift plan with an exclusion zone drawn around all rooftop equipment.